HEATMISER CONTROLS

Heatmiser neoStat V3 Programmable Smart Thermostat 230V

The standard neo zone thermostat.

A 230V smart thermostat for UFH and radiator zones. Use it as a programmable thermostat or a dedicated timer, and add a neoHub (2nd generation or later) for control from the neoApp.

CODES

HM-NEOSTAT-V3-W, -B, -S

PRODUCT



01 · IN THE BOX

What you get

- neoStat V3 thermostat
- Fixing screws

02 · YOU WILL NEED

Tools and materials

- Small screwdrivers
- 35mm deep wall back box
- Voltage tester

03 · SAFETY

Before you start

- Isolate the mains supply and prove it dead before removing a front plate or wiring any connection.
- A qualified electrician must make the final mains connections, to BS 7671.
- For indoor, dry locations only. Keep within the stated voltage and switching ratings.

04 · INSTALLATION

Fit it in 8 steps.

1. Choose a position away from draughts, direct sun and heat sources.
2. Isolate the supply to the heating controls and prove it dead.
3. Sink a standard 35mm deep back box and bring in the thermostat cable, plus the floor probe cable if used.
4. Wire to the zone terminals of the wiring centre per the Heatmiser diagram supplied.
5. Fit the thermostat to the back box and restore power.
6. Set it up as a thermostat or timer, and choose the sensing mode (air, remote air or floor).
7. To add app control, pair it to the neoHub from the neoApp.
8. Set the clock and comfort levels.

05 · TESTING AND COMMISSIONING

Test, check, then hand over

- [x] Raise the set temperature above room temperature and check the zone responds at the wiring centre.
- [x] If paired, check it appears in the neoApp and responds to an app change.

06 · CARE AND MAINTENANCE

Keep it working

- Wipe with a dry cloth only.

07 · WORKS WITH

Parts that fit with it

- Heatmiser neoHub G3 for app control
- Heatmiser UH4 or UH8 Wiring Centre
- 10K Floor Probe (3m) for floor sensing

08 · MANUFACTURER DOCUMENTS

Official Heatmiser documents

Heatmiser neoStat V3 datasheet (official)
https://www.heatmiser.com/download/329/neo-datasheets/14830/neostat-v3-datasheet.pdf

09 · JOB RECORD

Fill in on site, keep for the handover

Site / room

Installed by

Date

Test result

Notes

SCAN ME

Watch how it works and fits

Point your phone camera at the code to watch the video.

QUESTIONS ON SITE?

sales@maxheatufh.com **07539 499069**

WEB
maxheatufh.com

DELIVERY
Order by 12pm for next working day delivery